Healside Technology Solutions
No.12(First Floor), Persiaran Mutiara 1, Pusat Komersial Bandar Tasek Mutiara, 14120 Simpang Ampat, Pulau Pinang
Website: www.healside.com.my

Date : 29/6/2026

Work Order : PROPOSE TO REPLACE AND UPGRADE TO NEW 3.0HP CEILING EXPOSED INVERTER (AC08 - MEZZANINE FLOOR)

Location : East Coast - Jalan Sultan Ismail_Kuala Terengganu

Work Order Details
- To dismantle exisiting air conditioner unit consist of indoor,outdoor & related accessories - To supply & deliver new 3.0hp ceiling exposed inverter c/w all related accessories Brand : **Daikin / Acson (30,000 Btu/hr)** - To supply and deliver 25 meter copper tube , insulation , drain pipe c/w related accessories - To supply and install 3 core wire from indoor to outdoor unit c/w all ted accessories - To provide installation for new unit consist of indoor & outdoor unit c/w related works - To make good plaster ceiling and normal patching - Testing and commissioning

Job summary : **To replace AC08 with a new unit 3HP at mezzanine floor**

Payment Term : 14 days upon completion

Working date : 2 weeks from the time Healside Technology confirm the work order to vendor

Healside Technology Solutions
No.12(First Floor), Persiaran Mutiara 1, Pusat Komersial Bandar Tasek Mutiara, 14120 Simpang Ampat, Pulau Pinang
Website: www.healside.com.my

WORK PHOTO

WORK PHOTO












NOTE:

Details existing unit (AC08):

- Barcode No: BC882618 (CIMB-RC1302-AC08)
- Serial No indoor : 20560906-05243
- Serial No outdoor : 20561403-54053
- HP : 2.5hp
- Length pipe : 70ft+-
- Aging Year : 2013
- Outdoor area : back building

Kuhan
Operation Director
Healside Technology Solutions